

Design Drawings

for the

October 2017 Storm Damage: Saco River

located in

Bartlett, New Hampshire

prepared for

Town of Bartlett

HEB Project # 2019-064
 Issued: September 24, 2019

Revised: July 10, 2020

Applicant: Town of Bartlett
 56 Town Hall Road
 Intervale, NH 03845

Owners: Blaine & Patricia Rogerson
 PO Box 184
 Bartlett, NH 03812


George Family Irrevocable Trust
 c/o Jessica G. Spaulding
 PO Box 188
 Bartlett, NH 03812

Ian & Hayley Trill
 15 Holmfield Ave/South Shields
 TYNE+WEAR, NE346U



Todd, Mark, Paul, Mathew, Nicholas & Kimberly Seavey
 PO Box 90
 Conway, NH 03818

Sheet Index


Number	Sheet	Sheet Name	Latest Issue
1.	C0.01	Cover Sheet	07/10/2020
2.	C1.00	Overall Project Location Plan	07/10/2020
3.	C1.01	Erosion & Sediment Control Plan - Cobb Farm Road	07/10/2020
4.	C1.11	Erosion & Sediment Control Plan - River St. Bridge (Area 1)	07/10/2020
5.	C1.12	Erosion & Sediment Control Plan - River St. Bridge (Area 2)	07/10/2020
6.	C1.21	Site Plan - Cobb Farm Road	07/10/2020
7.	C1.31	Site Plan - River St. Bridge (Area 1)	07/10/2020
8.	C1.32	Site Plan - River St. Bridge (Area 2)	07/10/2020
9.	C3.11	Cross Sections: Cobb Farm Road-STA. 1+00-4+50	07/10/2020
10.	C3.21	Cross Sections: River St. Bridge-STA. 3+50-7+50	07/10/2020
11.	C3.22	Cross Sections: River St. Bridge-STA. 11+00-14+00	07/10/2020
12.	C3.23	Cross Sections: River St. Bridge-STA. 14+50-15+00	07/10/2020
13.	C5.11	Construction Details - General	07/10/2020




Engineer/Surveyor





HEB Engineers, Inc.
 www.hebengineers.com
 NH Office (603) 356-6936
 Post Office Box 440
 North Conway, NH 03860
 ME Office (207) 803-8265
 Post Office Box 343
 Bridgton, ME 04009





1 inch = 300 feet
(1 : 3600)

Copyright	2020	HEB Engineers, Inc.	
No.	Revision	DATE	BY
1	Revised per NRCS, NHDES & LAC comments	07/10/20	TBG/DDC



HEB Engineers, Inc.
www.hebengineers.com
NH Office (603) 356-6936
Post Office Box 440
North Conway, NH 03860
ME Office (207) 803-8265
Post Office Box 343
Bridgton, ME 04009


SURVEYED BY	MPM/SPD/DW/ALT
DESIGNED BY	TBG
DRAWN BY	TBG/DDD
CHECKED BY	JMM
FIELD BOOK	359
SCALE	1" = 300'
DATE	09/24/2019

Overall Project Location Plan
for the
October 2017 Storm Damage
on the
Saco River
located in & prepared for the
Town of Bartlett, New Hampshire

Control-Point Table				
Point #	Description	Northing	Easting	Elevation
1	MAGNAIL	576799.64	1077602.50	729.03
2	MAGNAIL	576930.48	1077745.03	725.87
3	MAGNAIL	576931.34	1078122.25	721.73
4	MAGNAIL	576811.42	1078525.77	723.19
5	MAGNAIL	576595.49	1078858.56	719.79
6	MAGNAIL	575945.79	1079057.09	714.33
7	MAGSPIKE	576365.25	1079143.12	718.84

Survey Notes

1. Site features and topography are per a field survey performed July 2019; under the direct supervision of Kevin L. Tilton, LLS #979; using a Leica TS16 robotic total station and Leica Viva Series GPS/GNSS receivers; and conforming with the technical standards for topographic surveys per the NH Code of Administrative Rules of the Board of Licensure for Land Surveyors.
2. Orientation is grid. Coordinate grid is NAD83, established with GPS observations tied to the NGS CORS network.
3. Contour interval = 2 ft. Vertical datum is NAVD88 tied to NGS benchmark P 7 1933 on the west abutment of the railroad bridge known as "Second Iron" over the Saco River.
4. This plan does not represent a complete boundary survey by HEB. Boundary information shown is per Bartlett tax maps.
5. Jurisdictional wetlands shown were delineated by Gregory W. Howard, CWS of North Country Soil Services on July 24, 2019, and located by HEB.



General Erosion-Control Requirements:

The primary intent of the erosion control requirements and the construction sequence is to stage the project in a manner that will minimize the potential for erosion and the potential negative effects associated therewith. The Engineer shall be contacted and the plan shall be amended if the intent is not being achieved.

1. Erosion control definitions:
 - "Strip topsoil": Excavate topsoil, screen, and stockpile.
 - "Seed(ing)": Adjust ph, apply fertilizer, sow the seed mixture, apply mulch (or erosion control matting), apply tackifier.
 - "Significant rainfall event": more than 1/4-inch of rain.
2. Install all erosion control measures prior to earthwork operation and maintain all erosion control measures and seeded embankments during construction. Erosion control shall be removed only upon the establishment of all vegetated areas.
3. All drainage structure inlets shall be protected using inlet protection or catch basin inserts.
4. Erosion control measures shall be implemented complying with the Best Management Practices (BMPs) of the "New Hampshire Stormwater Management Manual, Volume 2, Post-Construction Best Management Practices Section & Design," by the NHDES, USDA SCS, and Rockingham County Conservation District, latest edition.
5. Do not disturb areas outside the limits of proposed work. Areas disturbed by the Contractor's operations shall be restored to their original condition at the Contractor's expense. All areas disturbed during construction not covered with buildings, structures or pavement shall receive four (4) inches of loam and seed.
6. The downhill side of all stockpiles shall be encircled with silt fence.
7. All ditches, swales, and other areas of concentrated flow shall be stabilized prior to directing flow to them. Inlet protection to be installed prior to directing flow to storm drains.
8. Before weekends, and if a significant rainfall event is anticipated during the construction of the cut/fill embankments, a temporary berm shall be constructed along the top of the fill embankments, and temporary slope drains (pipes) with temporary stone outlet aprons shall be installed at the base of the slopes.
9. The maximum time that any disturbed areas shall be left unstabilized shall be 14 days.
10. The smallest practical area shall be disturbed to complete the required construction, but no more than 5 acres at any one time.
11. Lot disturbance, other than that shown on the approved plans, shall not commence until after the roadway and the associated drainage is complete and stable.
12. An area shall be considered stable if one of the following has occurred:
 - A. Base course gravels have been installed in areas to be paved;
 - B. A minimum of 85 percent vegetated growth has been established;
 - C. A minimum of 3 inches of non-erosive material such as stone or riprap has been installed; or
 - D. Erosion control blankets have been properly installed.
13. All erosion control measures shall be inspected weekly, and after every 0.25 inches or greater rainfall within a 24-hour period.
14. All roadways/parking areas and cut and fill slopes shall be stabilized within 72 hours of achieving finished grade.
15. Precaution shall be taken throughout the duration of construction activity to prevent, abate, and control the emission of fugitive dust, including but not limited to, wetting, covering, shielding, or vacuuming.
16. The project must meet the requirements and intent of RSA 430:53 and Agr 3800 relative to invasive species.
17. Temporary water diversions (swales, basins, etc.) must be used as necessary until areas are stabilized.
18. Detention basins and swales shall be installed before rough grading at the site.

Critical Erosion Areas:

Temporary seeding and/or mulching shall be used to protect exposed critical areas during construction. The following areas are particularly susceptible to erosion and shall receive extra attention when being inspected and maintained:

1. The larger cut and fill areas along the road and driveways.
2. Areas not worked or not to be worked for 3 weeks.
3. Areas of concentrated flow such as the ditches, swales, and toe of uphill facing slopes.
4. Stormwater ponds and level spreaders.

Seeding Notes:

1. Seed mixture: Prior to construction, submit certification from seed supplier that the mixture complies with the requirements. Include the requirements on the certification.
2. Prepare subsoil by eliminating uneven areas; removing foreign materials, weeds, and other undesirable plants and their roots; scarifying subsoil to a depth of 3 inches.
3. Spread loam to yield a minimum depth of 4 inches after rolling. Rake smooth to remove stones and roots. Loam shall consist of loose friable topsoil with no admixture of refuse or material toxic to plant growth. Loam shall be generally free from stones, lumps, stumps, subsoil, roots, and weeds or similar objects larger than 2 inches in greatest diameter. The term as used herein shall mean that portion of the soil profile defined technically as the "A" horizon by the Soil Science Society of America. The minimum and maximum pH value shall be from 5.5 to 7.6. Loam shall contain a minimum of 3 percent, and a maximum of 10 percent, of organic matter as determined by loss by ignition. Not more than 65 percent shall pass a No. 200 sieve as determined by the wash test in accordance with ASTM D 1140. In no instance shall more than 20 percent of that material passing the No. 4 sieve consist of clay size particles.
4. Apply agricultural limestone at a rate of 100 lbs, per 1000 sf.
5. Apply commercial grade 10-10-10 fertilizer at a rate of 10 lbs, per 1000 sf.
6. Sow uniformly with last year's crop of the local natural resource conservation service's "conservation mix" at a rate of 0.5lbs/1000 sf. Mixture is to have a germination rate of not less than 80 percent, and a purity of not less than 85 percent.
7. Roll seeded area with hand roller.
8. All ditches shall receive erosion control matting.

Temporary:

1. Bedding: Remove stones and trash that will interfere with seeding the area. Where feasible, till the soil to a depth of about 3 inches to prepare a seedbed and mix fertilizer into the soil. The seedbed should be left in a firm and smooth condition. The last tillage operation should be performed across the slope wherever practical.
2. Fertilizers: Fertilizer should be uniformly spread over the area prior to being incorporated into the soil. A minimum of 300 pounds per acre (7 pounds per 1,000 square feet) of 10-10-10 fertilizer, or its equivalent, should be applied.
3. Where it is impracticable to incorporate fertilizer and seed into moist soil, the seeded area should be mulched to facilitate germination.
4. Seed Mixture: Use any of the following:

Species	Per Acre	Per 1,000 s.f.	Dates	Depth
Winter Rye	112 lbs.	2.5 lbs.	8/15-9/5	1 inch
Oats	80 lbs.	2.0 lbs.	Spring-5/15	1 inch
Annual Ryegrass	40 lbs.	1.0 lb.	4/15-9/15	1/2 inch
Perennial Ryegrass	30 lbs.	0.7 lbs.	4/1-6/1 or 8/15-9/15	1/2 inch
5. Maintenance: If seeding fails to grow, it may need to be re-established to provide adequate erosion control. If weeds become a problem, they may need to be controlled by mowing.

Winter Construction Notes:

1. All proposed vegetated areas which do not exhibit a minimum of 85 percent vegetative growth by October 15th, or which are disturbed after October 15th, shall be stabilized by seeding and installing erosion control blankets on slopes greater than 3:1, and seeding and placing 3 to 4 tons of mulch per acre, secured with anchored netting, elsewhere. The installation of erosion control blankets or mulch and netting shall not occur over accumulated snow or on frozen ground and shall be completed in advance of thaw or spring melts.
2. All ditches or swales which do not exhibit 85 percent vegetative growth by October 15th, or which are disturbed after October 15th, shall be stabilized temporarily with stone or erosion control blankets appropriate for the design flow conditions.
3. After November 15th, incomplete road or parking surfaces, where work has stopped for the winter season, shall be protected with a minimum of 3 inches of crushed gravel per NHDOT Item 304.3.

Construction Sequence (Bank Stabilization):


NHDES requires that certain steps be taken in order to minimize the erosion of soil within the limits of work. These measures are integral to the successful restoration of the project site. Listed below is a potential construction sequence that would achieve this goal. The specific means and methods are to be determined by the Contractor, but must meet the requirements of the approved Wetlands Permit and supporting Contract Documents. Contractor's proposed construction sequence shall be approved by Engineer prior to construction.

1. Install erosion and sediment control measures prior to any earth moving activity that will influence or affect stormwater runoff.
2. Clear and grub area necessary for construction access.
3. Install temporary siltation measures and cofferdams in the channel.
4. Place new riprap in noted locations and repair existing riprap.
5. Remove water diversion measures.
6. Stabilize site and disturbed areas. Leave erosion and sediment control materials in place until the project area has stabilized.



U.S. Fish and Wildlife Classification:

PSSIE Palustrine, Scrub-Shrub, Broad-Leaved Deciduous, Seasonally Flooded/Saturated
R3UBTH Riverine, Upper Perennial, Unconsolidated Bottom, Cobble-Gravel, Permanently Flooded

Legend		Wetland Impacts (Bank-Stabilization)	
--- 410 ---	Existing major contour	[Solid Blue Box]	Permanent Wetland Impact Area (Bank Stabilization) = 551 SF
--- 408 ---	Existing minor contour	[Blue Hatched Box]	Permanent Wetland Impact Area (Cobble Removal) = 0 SF
- - - 410 - - -	Proposed major contour	[Blue Dotted Box]	Temporary Wetland Impact Area = 419 SF
- - - 408 - - -	Proposed minor contour		
---	Edge of water		
[Riprap Symbol]	Riprap		
[Dashed Line Symbol]	Delineated Wetland		Total Wetland Impact Area = 970 SF
[Wavy Line Symbol]	Existing/Proposed Vegetation Line		
[Dotted Line Symbol]	Silt Fence	---	Stream Channel Impact Length = 0 LF
[Wavy Line Symbol]	Proposed Cofferdam	- - - - -	Stream Bank Impact Length = 44 LF
[Cross-hatched Symbol]	Proposed erosion control matting		Total Stream Impact Length = 44 LF



Copyright		2020		HEB Engineers, Inc.	
No.	Revision	DATE	BY		
1	Revised per NRCS, NHDES & LAC comments	07/10/20	TBG/DDD		




HEB Engineers, Inc.
www.hebengineers.com
NH Office (603) 356-6936
Post Office Box 440
North Conway, NH 03860
ME Office (207) 803-8265
Post Office Box 343
Bridgton, ME 04009

SURVEYED BY	MPM/SPR/DW/ALT
DESIGNED BY	TBG
DRAWN BY	TBG/DDD
CHECKED BY	JMM
FIELD BOOK	359
SCALE	1" = 30'
DATE	09/24/2019

Erosion & Sediment Control Plan - Cobb Farm Road
for the
October 2017 Storm Damage
on the
Saco River
located in & prepared for the
Town of Bartlett, New Hampshire

2019-064
C1.01
SHEET 3 OF 13



Construction Sequence:
 NHDES requires that certain steps be taken in order to minimize the erosion of soil within the limits of work. These measures are integral to the successful restoration of the project site. Listed below is a potential construction sequence that would achieve this goal. The specific means and methods are to be determined by the Contractor, but must meet the requirements of the approved Wetlands Permit and supporting Contract Documents. Contractor's proposed construction sequence shall be approved by Engineer prior to construction.

1. Install erosion and sediment control measures prior to any earth moving activity that will influence or affect stormwater runoff.
2. Clear and grub area necessary for construction access.
3. Install temporary siltation measures and cofferdams in the channel.
4. Remove river cobble in designated areas.
5. Place new riprap in noted locations and repair existing riprap.
6. Remove water diversion measures.
7. Stabilize site and disturbed areas. Leave erosion and sediment control materials in place until the project area has stabilized.

U.S. Fish and Wildlife Classification:

PSS1E	Palustrine, Scrub-Shrub, Broad-Leaved Deciduous, Seasonally Flooded/Saturated
R2US1A	Riverine, Upper Perennial, Unconsolidated Shore, Cobble-Gravel, Temporarily Flooded
R2UB1H	Riverine, Upper Perennial, Unconsolidated Bottom, Cobble-Gravel, Permanently Flooded


Legend

	Existing major contour
	Existing minor contour
	Proposed major contour
	Proposed minor contour
	Edge of water
	Riprap
	Delineated Wetland
	Existing/Proposed Vegetation Line
	Silt Fence
	Proposed Cofferdam
	Proposed erosion control matting



Wetland Impacts (Levee/Berm)

	Permanent Wetland Impact Area (Bank Stabilization) = 8,377 SF
	Permanent Wetland Impact Area (Cobble Removal) = 0 SF
	Temporary Wetland Impact Area = 2,451 SF
Total Wetland Impact Area = 10,827 SF	
	Stream Channel Impact Length = 371 LF
	Stream Bank Impact Length = 383 LF
Total Stream Impact Length = 754 LF	

- Survey Notes**
1. Site features and topography are per a field survey performed July 2019; under the direct supervision of Kevin L. Tilton, LLS #979; using a Leica TS16 robotic total station and Leica Viva Series GPS/GNSS receivers; and conforming with the technical standards for topographic surveys per the NH Code of Administrative Rules of the Board of Licensure for Land Surveyors.
 2. Orientation is grid. Coordinate grid is NHSPC - NAD83, established with GPS observations tied to the NGS CORS network.
 3. Contour interval = 2 ft. Vertical datum is NAVD83 tied to NGS benchmark P 7 1933 on the west abutment of the railroad bridge known as "Second Iron" over the Saco River.
 4. This plan does not represent a complete boundary survey by HEB. Boundary information shown is per Bartlett tax maps.
 5. Jurisdictional wetlands shown were delineated by Gregory W. Howard, CWS of North Country Soil Services on July 24, 2019, and located by HEB.



Copyright	2020	HEB Engineers, Inc.	
No.	Revision	DATE	BY
1	Revised per NRCS, NHDES & LAC comments	07/10/20	TBG/DDD



HEB Engineers, Inc.
 www.hebengineers.com
 NH Office (603) 356-6936
 Post Office Box 440
 North Conway, NH 03860
 ME Office (207) 803-8265
 Post Office Box 343
 Bridgton, ME 04009

SURVEYED BY	MPM/SPD/DW/ALT
DESIGNED BY	TBG
DRAWN BY	TBG/DDD
CHECKED BY	JMM
FIELD BOOK	359
SCALE	1" = 30'
DATE	09/24/2019

Erosion & Sediment Control Plan - River St. Bridge (Area 1)
 for the
October 2017 Storm Damage
 on the
Saco River
 located in & prepared for the
Town of Bartlett, New Hampshire

T.L. 5COBR/23RW2
Sandra J. Mead Trust
c/o Sandra J. Mead
PO Box 73
Bartlett, NH 03812

T.L. 5COBR/23LW0
Todd, Mark, Paul, Matthew,
Nicholas, & Kimberly Seavey
PO Box 90
Conway, NH 03818

T.L. 5COBR
Town of Bartlett
56 Town Hall Rd.
Intervale, NH 03845


T.L. 5COBR
Town of Bartlett
56 Town Hall Rd.
Intervale, NH 03845

T.L. 5COBR/AREO
Robert C. Galligan
21 Brander Rd.
Attleboro, MA 02703

T.L. 5VLLG/RIV550
Town of Bartlett
56 Town Hall Rd.
Intervale, NH 03845

T.L. 5VLLG/RIV560
Laura McGrath &
Robert Hajjar
7 Harris Ave.
Wellesley, MA 02481

T.L. 5VLLG/GEO12A
George Family Irrevocable Trust
c/o Jessica G. Spaulding
PO Box 188
Bartlett, NH 03812




U.S. Fish and Wildlife Classification:



PSSIE	Palustrine, Scrub-Shrub, Broad-Leaved Deciduous, Seasonally Flooded/Saturated
R3US1A	Riverine, Upper Perennial, Unconsolidated Shore, Cobble-Gravel, Temporarily Flooded
R3UB1H	Riverine, Upper Perennial, Unconsolidated Bottom, Cobble-Gravel, Permanently Flooded
PFO1E	Palustrine, Forested, Broad-Leaved Deciduous, Seasonally Flooded/Saturated

Legend

--- 410 ---	Existing major contour		Permanent Wetland Impact Area (Cobble Removal) = 48,197 SF
--- 408 ---	Existing minor contour		Total Wetland Impact Area = 48,197 SF
--- 410 ---	Proposed major contour		Stream Channel Impact Length = 759 LF
--- 408 ---	Proposed minor contour		Stream Bank Impact Length = 911 LF
---	Edge of water		Total Stream Impact Length = 1,670 LF
	Riprap		
	Delineated Wetland		
	Existing/Proposed Vegetation Line		
	Silt Fence		
	Proposed Cofferdam		
	Proposed erosion control matting		



Copyright	2020	HEB Engineers, Inc.	
No.	Revision	DATE	BY
1	Revised per NRCS, NHDES & LAC comments	07/10/20	TBG/DD




HEB Engineers, Inc.
www.hebengineers.com
NH Office (603) 356-6936
Post Office Box 440
North Conway, NH 03860
ME Office (207) 803-8265
Post Office Box 343
Bridgton, ME 04009

SURVEYED BY	MPM/SP/DW/ALT
DESIGNED BY	TBG
DRAWN BY	TBG/DD
CHECKED BY	JMM
FIELD BOOK	359
SCALE	1" = 30'
DATE	09/24/2019


Erosion & Sediment Control Plan - River St. Bridge (Area 2)
for the
October 2017 Storm Damage
on the
Saco River
located in & prepared for the
Town of Bartlett, New Hampshire

Control-Point Table				
Point #	Description	Northing	Easting	Elevation
1	MAGNAIL	576799.64	1077602.50	729.03
2	MAGNAIL	576930.48	1077745.03	725.87
3	MAGNAIL	576931.34	1078122.25	721.73
4	MAGNAIL	576811.42	1078525.77	723.19
5	MAGNAIL	576595.49	1078858.56	719.79
6	MAGNAIL	575945.79	1079057.09	714.33
7	MAGSPIKE	576365.25	1079143.12	718.84





General Notes:

- The location of existing utilities are approximate and have not been independently verified. Contact "Dig-Safe" prior to any excavation at 1-888-344-7233 and any other utility owners for accurate utility marking. Contractor to pay for all damages which may occur by failure to locate and preserve any utilities.
- Contractor is responsible for all work shown on the drawings, unless otherwise noted.
- Coordinate construction activities, materials storage and equipment staging area with Engineer.
- All disturbed areas within project limits not covered by hard surfaces or landscaping shall be finished with 4" of loam (NHDOT Item 641) and turf establishment (NHDOT Item 646.31).
- The work shall be done during low water periods or "in the dry." There shall be no excavation in free flowing water.
- Erosion and sediment controls shall be installed prior to any excavation.
- All dredged material shall be placed outside NHDES Wetlands Bureau Jurisdiction.
- All disturbed areas shall be stabilized within 3 days of final grading.
- Erosion and sediment controls shall remain in place until disturbed areas are fully stabilized.
- All work shall conform to the latest edition of the NHDOT Standard Specifications for Road & Bridge Construction at the time of plan issuance.
- Perform all work in compliance with federal, state, and local permit approvals. Copies of all permit approvals shall be maintained at the project site.
- Site security and job safety are the sole responsibility of the contractor. All construction activities shall comply with OSHA standards and local requirements.
- Provide submittals (gradations, proctors, product data, etc.) as directed by the Owner and Engineer for all materials to be incorporated into the work.
- Provide field testing of installed materials (compaction, density, leakage, etc) as directed by the Owner and Engineer at no cost to the Owner.
- The Engineer shall have full access to the site when the work is in preparation and progress. They may observe the work on a periodic or full-time basis.
- Provide detailed construction schedule to the Owner and Engineer prior to construction.



Copyright	2020	HEB Engineers, Inc.	
No.	Revision	DATE	BY
1	Revised per NRCS, NHDES & LAC comments	07/10/20	TBG/DDD





HEB Engineers, Inc.
www.hebengineers.com
NH Office (603) 356-6936
Post Office Box 440
North Conway, NH 03860
ME Office (207) 803-8265
Post Office Box 343
Bridgton, ME 04009

SURVEYED BY	MPM/SPP/DW/ALT
DESIGNED BY	TBG
DRAWN BY	TBG/DDD
CHECKED BY	JMM
FIELD BOOK	359
SCALE	1"=30'
DATE	09/24/2019



Site Plan - Cobb Farm Road
for the
October 2017 Storm Damage
on the
Saco River
located in & prepared for the
Town of Bartlett, New Hampshire

2019-064

C1.21












Copyright	2020	HEB Engineers, Inc.	
No.	Revision	DATE	BY
1	Revised per NRCS, NHDES & LAC comments	07/10/20	TBG/DD




HEB Engineers, Inc.
www.hebengineers.com
NH Office (603) 356-6936
Post Office Box 440
North Conway, NH 03860
ME Office (207) 803-8265
Post Office Box 343
Bridgton, ME 04009

SURVEYED BY	MPM/SP/DW/ALT
DESIGNED BY	TBG
DRAWN BY	TBG/DD
CHECKED BY	JMM
FIELD BOOK	359
SCALE	1" = 30'
DATE	09/24/2019

Site Plan - River St. Bridge (Area 2)
for the
October 2017 Storm Damage
on the
Saco River
located in & prepared for the
Town of Bartlett, New Hampshire













Copyright	2020	HEB Engineers, Inc.	
No.	Revision	DATE	BY
1	Revised per NRCS, NHDES & LAC comments	07/10/20	TBG/DDD



HEB Engineers, Inc.
www.hebengineers.com
NH Office (603) 356-6936
Post Office Box 440
North Conway, NH 03860
ME Office (207) 803-8265
Post Office Box 343
Bridgton, ME 04009



SURVEYED BY	MPM/SPP/DWM/ALT
DESIGNED BY	TBG
DRAWN BY	TBG/DDD
CHECKED BY	JMM
FIELD BOOK	359
SCALE	1"=20'
DATE	09/24/2019

Cross Sections: Cobb Farm Road-STA. 1+00-4+50
for the
October 2017 Storm Damage
on the
Saco River
located in & prepared for the
Town of Bartlett, New Hampshire



1 inch = 20 feet
(1 : 240)



Copyright	2020	HEB Engineers, Inc.	
No.	Revision	DATE	BY
1	Revised per NRCS, NHDES & LAC comments	07/10/20	TBG/DDC





HEB Engineers, Inc.
www.hebengineers.com
NH Office (603) 356-6936
Post Office Box 440
North Conway, NH 03860
ME Office (207) 803-8265
Post Office Box 343
Bridgton, ME 04009

SURVEYED BY	MPM/SPP/DW/ALT
DESIGNED BY	TBG
DRAWN BY	TBG/DDC
CHECKED BY	JMM
FIELD BOOK	359
SCALE	1"=20'
DATE	09/24/2019

Cross Sections: River St. Bridge—STA. 3+50-7+50
for the
October 2017 Storm Damage
on the
Saco River
located in & prepared for the
Town of Bartlett, New Hampshire






Copyright		2020		HEB Engineers, Inc.	
No.	Revision	DATE	BY		
1	Revised per NRCS, NHDES & LAC comments	07/10/20	TBG/DDC		





HEB Engineers, Inc.
 www.hebengineers.com
 NH Office (603) 356-6936
 Post Office Box 440
 North Conway, NH 03866
 ME Office (207) 803-8265
 Post Office Box 343
 Bridgton, ME 04009

SURVEYED BY	MPM/SPD/DW/ALT
DESIGNED BY	TBG
DRAWN BY	TBG/DDC
CHECKED BY	JMM
FIELD BOOK	359
SCALE	1"=20'
DATE	09/24/2019

Cross Sections: River St. Bridge-STA. 11+00-14+00
 for the
 October 2017 Storm Damage
 on the
 Saco River
 located in & prepared for the
 Town of Bartlett, New Hampshire












Copyright	2020	HEB Engineers, Inc.	
No.	Revision	DATE	BY
1	Revised per NRCS, NHDES & LAC comments	07/10/20	TBG/DDC




HEB Engineers, Inc.
www.hebengineers.com
NH Office (603) 356-6936
Post Office Box 440
North Conway, NH 03860
ME Office (207) 803-8265
Post Office Box 343
Bridgton, ME 04009

SURVEYED BY	MPM/SPP/DW/AT
DESIGNED BY	TBG
DRAWN BY	TBG/DDC
CHECKED BY	JMM
FIELD BOOK	359
SCALE	1"=20'
DATE	09/24/2019

Cross Sections: River St. Bridge-STA. 14+50-15+00
for the
October 2017 Storm Damage
on the
Saco River
located in & prepared for the
Town of Bartlett, New Hampshire



Copyright	2020	HEB Engineers, Inc.	
No.	Revision	DATE	BY
1	Revised per NRCS, NHDES & LAC comments	07/10/20	TBG/DDD



HEB Engineers, Inc.
 www.hebengineers.com
 NH Office (603) 356-6936
 Post Office Box 440
 North Conway, NH 03860
 ME Office (207) 803-8265
 Post Office Box 343
 Bridgton, ME 04009

SURVEYED BY	MPM/SPD/DW/ALT
DESIGNED BY	TBG
DRAWN BY	TBG/DDD
CHECKED BY	JMM
FIELD BOOK	359
SCALE	AS NOTED
DATE	09/24/2019